



SHEET SPEC ID LIST	
SPEC ID	DESCRIPTION
13 3100	FABRIC STRUCTURES
13 3416	ALL ALUMINUM FRAMED BLEACHER
13 3417	PRESS BOX
A601	10-4500- AUTOMATED EXTERNAL DEFIBRILLATOR AND CABINET

KEYNOTES - FLOOR PLAN		
NO	NOTE	REV.
01	PROVIDE CFRP-1s ADJACENT TO MOP BASIN EACH SIDE FOR 48" UP TO 48" AFF. REFER TO MOUNTING HEIGHTS SHEETS	
02	FLOOR DRAIN; REFER TO MEP.	
03	STOOR; REFER TO STRUCTURAL	
04	FABRIC SHADE STRUCTURE. COORDINATE WITH BLEACHER CONTRACTOR 1	

REVISION SCHEDULE		
NO.	DESCRIPTION	DATE
1	ADDENDUM #1	8/27/25

GENERAL NOTES - FLOOR PLAN

- A. FOR TYPICAL BARRIER FREE TOILET ROOM TYPES AND ACCESSORIES REQUIREMENTS AND LOCATIONS SEE DWG G120.
- B. FOR TYPICAL HOUSEKEEPING CLOSETS ACCESSORIES REQUIREMENTS AND MOUNTING LOCATIONS SEE DWG G210.
- C. ALL PARTITION TYPES ARE "M8" TYPICALLY UNLESS OTHERWISE NOTED.
- D. COORDINATE PARTITION FIRE RATED REQUIREMENTS AS INDICATED ON LIFE SAFETY PLANS.
- E. TYPICALLY INSTALL SOAP DISPENSERS AND PAPER TOWEL DISPENSER AT ALL SINKS UNLESS NOTED OTHERWISE.
- F. PROVIDE WALL REINFORCEMENT AT WALL-MOUNTED SHELVES AND STORAGE UNITS, MARKER BOARDS, BULLETIN BOARDS, TACK BOARDS, TELEVISIONS AND OTHER CONTRACTOR OR OWNER FURNISHED WALL-MOUNTED ITEMS.
- G. PROVIDE AND COORDINATE TERMITE CONTROL TREATMENT PRIOR TO VAPOR BARRIER INSTALLATION. SEE SPECIFICATION FOR MORE INFORMATION.
- H. COORDINATE DIMENSIONS WITH ASTERISK (IE - *X-X*) WITH EQUIPMENT VENDOR.
- I. FOR INTERIOR METAL STUD CONSTRUCTION ALL DIMENSIONS ARE TO FACE OF METAL STUDS UNLESS NOTED OTHERWISE.
- J. ALL DIMENSIONS INDICATED AS 'CLEAR' ARE TO FACE OF FINISH (GYPSUM, TILE, ETC.).
- K. ALL MASONRY DIMENSIONS ARE TO FACE OF MASONRY UNLESS NOTED OTHERWISE.
- L. ALL EXTERIOR OPENING DIMENSIONS ARE ROUGH OPENINGS.
- M. COORDINATE ALL FLOOR OPENING DIMENSIONS AND CLEARANCES FOR DUCTWORK WITH MECHANICAL CONTRACTOR - TYPICAL.
- N. COORDINATE AND/OR CONFIRM ANY DIMENSIONAL DISCREPANCIES WITH ARCHITECT PRIOR TO INSTALLATION.

GENERAL NOTES - INTERIOR ELEVATIONS

- A. REFER TO A620 & A621 FOR STANDARD CASEWORK ELEVATIONS AND CONSTRUCTION.
- B. ALL WALL SURFACES TO BE (HPC-1) UNLESS NOTED OTHERWISE.
- C. PROVIDE LEVEL 5' DRYWALL FINISH AT ALL APPLIED GRAPHICS AND WRITABLE WALL SURFACE LOCATIONS.
- D. PROVIDE WALL REINFORCEMENT AT ALL WALL MOUNTED ITEMS.
- E. ANY EXPOSED CABINET EDGE SHALL BE FINISHED EDGE TO MATCH ADJACENT CABINET FINISH.
- F. SEE SHEET G120 FOR ALL TOILET RIM HEIGHTS AND ACCESSORY MOUNTING HEIGHTS.



710 South 2nd Street, 8th Floor
Minneapolis, MN 55401
phone: (612) 746-4260

www.jlgarchitects.com
copyright © 2025



REVISION SCHEDULE		
NO.	DESCRIPTION	DATE
1	ADDENDUM #1	8/27/25

CHATHAM COUNTY
ANCHOR PARK CONCESSION AND TEAM ROOM FACILITY
 PORT WENTWORTH, GA

DATE	7/31/2025
PHASE	BID SET
PROJECT	24117.01
SHEET	A203
FLOOR PLAN - BLEACHERS	

8/27/2025 8:21:24 AM